

# Flat Rock Dam — Manayunk Canal Betterment Project

*Water Quality | Safety | Ecological Integrity*

**AWWA PA Section | Fall 2023 Joint Technical Conference**  
**Tuesday, October 24<sup>th</sup>, 2023 | 1:30 PM**

**PHILADELPHIA**  
**WATER**  
— DEPARTMENT —



**Rowan University**

HENRY M. ROWAN

COLLEGE OF ENGINEERING

---

---

**VILLANOVA UNIVERSITY**

COLLEGE OF ENGINEERING

---

---



**CENTER FOR RESILIENT  
WATER SYSTEMS**

**Ian McKane, EIT**

**B.S. Civil Engineering**

**M.S. Civil Engineering**

(Spatial and Temporal Trends in Infiltration, Soil Texture, and Nutrient Accumulation in Rain Gardens)

Construction Project Engineer for Flat Rock Dam

**PHILADELPHIA  
WATER**  
— DEPARTMENT —

# Outline

1. Project Background and History
2. Water Quality Improvements
3. Construction Timeline & Community Impact

*Disclaimer: This Presentation is provided as of October 17, 2023. If you are viewing this Presentation after that date, there may have been events that occurred subsequently that could have a material effect on the information that was presented. By presenting this information, PWD has not undertaken any obligation to update the information beyond the date of the presentation. Data and other information provided are not warranted as to completeness or accuracy and are subject to change without notice. This Presentation is provided for your information and convenience only.*





Philadelphia County

Manayunk Canal  
Schuylkill River

Montgomery County

Layers

Google 100%

600 m

Camera: 5,043 m

40°01'56"N 75°14'09"W 15 m





Philadelphia County

Montgomery County

Schuylkill River

Manayunk Canal

Manayunk Canal

Elite Sports Factory

CHO Care

Layers

3D





FLAT ROCK DAM MAIN SPILLWAY  
OWNED BY THE COMMONWEALTH OF PENNSYLVANIA

INLET CANAL WALL

MANAYUNK INLET CANAL

SCHUYLKILL RIVER  
(WATERS OF THE U.S.)

FISH LADDER OWNED BY THE  
COMMONWEALTH OF  
PENNSYLVANIA



MANAYUNK  
CANAL

LOCK NO 68

FEEDER STRUCTURE





# 1. Project Background

Mission Statement

Design Rationale and Sustainability

Historic Features: Past to Present

Environmental Impacts and Benefits

Construction Updates

Project Timeline

# 1. Project Background

## Project Mission

- To improve water quality in the Manayunk Canal
- To meet Dam safety compliance & regulations





FLAT ROCK DAM MAIN SPILLWAY  
OWNED BY THE COMMONWEALTH OF PENNSYLVANIA

INLET CANAL WALL

MANAYUNK INLET CANAL

SCHUYLKILL RIVER  
(WATERS OF THE U.S.)

FISH LADDER OWNED BY THE  
COMMONWEALTH OF  
PENNSYLVANIA



LOCK NO 68

MANAYUNK  
CANAL

FEEDER STRUCTURE

# Project background / Reasons for project

- Manayunk Canal has no connection to the Schuylkill River
- Canal is stagnant, leading to algae blooms and fish deaths
- Sediment, trash, and debris has accumulated upstream of the Gatehouse Structure
- Historic Gatehouse Structure has become unsafe
- Dam Repairs





Towpath

Bulkhead

Lock No. 68

Intake Channel

Accumulated Sediment

Manayunk Canal

Intake Channel Wall

Gatehouse Structure

Schuylkill River



# Schuylkill Navigation Company Port Carbon to Philadelphia, PA

Over 130 miles



Flat Rock Dam  
Constructed 1815  
Re-Constructed 1909



*Flat Rock  
Dam,  
Fairmount  
Park*



# Historic Features in Manayunk Canal

- Feeder Gatehouse Structure
- Lock No. 68
- Towpath (Schuylkill River Trail)
- 1.75 mile long Manayunk Canal
- Lock No. 69, 70

# Lock 68 and Feeder Structure Prior to 1918



Photo Courtesy of Adam E. Levine,  
Historical Consultant, Philadelphia  
Water Department



Lock 68 and  
Feeder Structure  
Circa 1918



Photo Courtesy of Adam E. Levine,  
Historical Consultant, Philadelphia  
Water Department

# Critical Drivers for Project Design



- Chapter 105 – PADEP Dams and Waterways
- Chapter 93 – PADEP Water Quality Standards
- PENNVEST Funding



# Sustainable Operations

- To be sustainable, the design solution must provide for:
  - Flow Control (Normal Operations and Flood Control) using manually operated gates
  - Debris collection and removal
  - Sediment management and removal
  - Regular inspections and maintenance

# Existing Conditions



Towpath

Bulkhead

Lock No. 68

Intake Channel

Accumulated Sediment

Manayunk Canal

Intake Channel Wall

Gatehouse Structure

Schuylkill River



# Proposed Conditions



Canal Intake Structure

Green Stormwater Basin

New Channel

Interpretive Historical Panel

Historic Features to Remain

Sluiceway

New Waste Weir


Green Stormwater Basins

New Access Drive

Lowered and Stabilized Canal Intake Channel Wall



# Proposed Conditions



Canal Intake Structure

Green Stormwater Basin

New Channel

Interpretive Historical Panel

Historic Features to Remain

Sluiceway

New Waste Weir

Green Stormwater Basins

New Access Drive

Lowered and Stabilized Canal Intake Channel Wall




# Prior to Construction

## Abandonment of Historic Features

- Canal ceased operations in the 1940s
- Lock gates were removed, and Lock 68 was bulkheaded in the 1970s
- Outlet arches of Feeder Structure were plugged
- Maintenance dredging and collection of debris ceased
- Brick Feeder Gatehouse was boarded up and abandoned

# Existing Conditions and Adverse Effects



-  No Longer Exists
-  Extremely Deteriorated
-  Conflicts With New Configuration
-  Requires Stability Improvements

Photo Courtesy of Adam E. Levine, Historical Consultant, Philadelphia Water Department



# Preservation and Mitigation

- Preserve what remains of pre-1918 structures - Lock 68 and Masonry Feeder Structure
- Cleaning (graffiti removal), Clearing of vegetation and Restoration of Preserved features
- Operating gears will be preserved in place to be seen from the towpath/trail
- Provide for interpretation of historic features from the towpath/trail
- Fencing to inhibit trespass
























# Upstream View from Sediment Area – Before and After





# Downstream View of Lock – Before and After





# View from Trail – Before and After





# Above View - Pre- and Post-Construction





# 2. Water Quality Improvements

Flat Rock Dam - Manayunk Canal Improvements Project



# Water Quality Concerns - *Algal Blooms*

- Frequent in Summer months
- Negative impact on water quality and aquatic organisms
- Taste and odor concerns for City's drinking water



Algal bloom during drought conditions in 1999  
(Upstream view at Lock Street)



Floating mats of benthic algae at Lock Street bridge  
(2006)



# Water Quality Concerns -

## *Downstream Drinking Water Intakes*



One city.  
Two rivers.  
Three treatment plants.



# Water Quality Concerns - *Flow Conditions*

- **Present conditions:**
  - Spring flow ranges from 3 – 5 cfs
  - Summer flow ranges from 1 – 3 cfs
  - Average velocity of 0.03 ft/s
- **Post-construction conditions:**
  - Flow ranges between 50 – 110 cfs
  - Average velocity between 0.3 – 0.5 ft/s



2011 summer flows over Lock Street (~1 cfs)



# Water Quality Concerns - *Improvement Benefits*

## Water Quality & Source Water Protection

- Flow diversion will:
  - Increase velocities
  - Decrease hydraulic residence time
  - Improve dissolved oxygen concentrations
  - Improve biological health of fisheries and aquatic organisms (mussels)
  - Reduce potential of harmful algal blooms



**Reintroduce Freshwater Mussels**





# 3. Construction Timeline & Community Impact

# Project Timeline

---

- Design Drawings Completed – Winter 2020
  - Bidding – Winter 2021
    - Contract Awarded to A.P. Construction Inc. for \$16,301,250.00
  - Notice to Proceed – March 2022
  
  - Project Construction Period:
    - Estimated 900 calendar days of construction
    - March 2022 to September 2024
-



# Gatehouse





# March 2022 - Start of Work - Gatehouse





# March 2022 - Start of Work – Upstream of Gatehouse





# April 2022 - Start of Work – Gatehouse Downstream





# May 2022 - Start of Work – Gatehouse Downstream





# May 2022 - Start of Work – Site Clearing






**May 2022**

**- Start of Work – Accessway Clearing One road in and out**





# Cofferdams





# June 2022

## - Install Upstream Channel Cofferddam





# July 2022

## - Install Upstream Channel Cofferdam





# July 2022

## - Install Upstream and River Cofferdam at Weir





# August 2022- Install Upstream Channel Cofferdam





# August 2022- Install Upstream Channel Cofferdam





# September 2022 - Install River Cofferddam at Weir





# September 2022 - Dewatering and Excavation, Turtle and Fish removal





# September 2022 - Bedrock Excavation for Weir





# September 2022 - Bedrock Excavation for Weir





# October 2022 - Installation of Post-tensioned Rock Anchors





# October 2022 - Excavation and Anchors at Bulkhead Wall and Canal Intake





# November 2022 - Beginning of Rebar and Formwork Installation, Impact or Storm Events





Weir






# November 2022 - First Concrete Pour for Weir foundation behind Existing Weir





# December 2022

## - Constructing new concrete weir behind existing weir





# December 2022 - Sign facing Schuylkill River Trail





# January 2023 - Continuing Weir Concrete Work





# Canal Intake





# February 2023 - Rebar, Formwork, and Concrete at Canal Intake Structure Foundation





# February 2023 - Demolition of old concrete weir





# February 2023 - Community Meeting





# March 2023 - Constructing bulkhead wall sections





# March 2023 - Rock preparation and anchor installation for weir





# March 2023 - Constructing bulkhead wall sections





# April 2023 - Demolition of old Dam portion wall for new wall cap





# April 2023 - Concrete pour for canal channel intake structure





# May 2023 - Impact of Storm Events on in river work





# June 2023 - Rebar, Formwork, and Concrete work for Weir





# June 2023 - Rebar, Formwork, and Concrete work for Weir





# June – July 2023 - Rebar, Formwork, and Concrete for Weir





# July 2023 - Rebar, Formwork, and Concrete work on Canal Channel Foundations





# July 2023 - Rebar, and Formwork Installation for Canal Intake





# August 2023 - Rebar, Formwork, and Concrete work on Weir





# August 2023 - Rebar, Formwork, and Concrete work on Canal Intake Structure, Gate Thimble Installation





# September 2023 - Concrete pours at Sluiceway and Weir





# September 2023 - Weir, Sluiceway, and Canal Intake Work Continues





# Community Impact

- Schuylkill River Trail Closure Required  
– September 2023 to January 2024





# September 2023 - Schuylkill River Trail Closure Signs





# September 2023 - Installation of Shoring for Bulkhead Wall Excavation





# October 2023 - Shoring and Tieback Anchor Installation





# October 2023 - Excavation, Shoring and Tieback Anchor Installation





# November 2023

- **Upcoming Work Progress**
  - **Finish shoring Installation and Excavation**
  - **Install and Test Post-tensioned Rock Anchors in bulkhead wall footings**
  - **Bulkhead Wall Concrete foundations**



# Community Impact

---

- Expected Project Completion:
  - September 2024



May 2022

Historic Gatehouse

Weir





September 2023



Historic Gatehouse

Weir



# Completed

Historic Gatehouse

Weir





# Flat Rock Dam — Manayunk Canal Betterment Project

Ian McKane, Construction Engineer for Flat Rock Dam  
[ian.mckane@phila.gov](mailto:ian.mckane@phila.gov), 267-250-1816  
[linkedin.com.in/ianmckane](https://www.linkedin.com/in/ianmckane)

*Project Updates:* [water.phila.gov/flat-rock](https://water.phila.gov/flat-rock)



# Flat Rock Dam — Manayunk Canal Betterment Project

*Water Quality | Safety | Ecological Integrity*

**AWWA PA Section | Fall 2023 Joint Technical Conference**  
**Tuesday, October 24<sup>th</sup>, 2023 | 1:30 PM**

**PHILADELPHIA**  
**WATER**  
— DEPARTMENT —



# Proposed Conditions



Canal Intake Structure

Green Stormwater Basin

New Channel

Interpretive Historical Panel

Historic Features to Remain

Sluiceway


New Waste Weir

Green Stormwater Basins

New Access Drive

Lowered and Stabilized Canal Intake Channel Wall





Manayunk Canal

Historic Features  
(Stabilized and Preserved)

Green Stormwater  
Basins

New Access Road

Sluiceway  
(For sediment management)

Channel  
(Conveys flow to Canal)

Waste Weir  
(Regulates high flow conditions)

Canal Intake Structure  
(Regulates flow to Canal)

Schuylkill River

Floating Debris Boom  
(Deflects large debris)



# December 2023 – September 2024

- **Upcoming Work Progress**
  - **Complete Bulkhead Wall**
  - **Remove Upstream Channel Cofferdam**
  - **Complete Canal Channel**



**Thank you!**

**Peter Reilly**, Construction Division Engineer

- [peter.reilly@phila.gov](mailto:peter.reilly@phila.gov), 215-200-1539

**Ian McKane**, Construction Engineer for Flat Rock Dam

- [ian.mckane@phila.gov](mailto:ian.mckane@phila.gov), 267-250-1816

**Amy Hopf**, Construction Liaison

- [amy.hopf@phila.gov](mailto:amy.hopf@phila.gov), 215-809-7201

***Project page for updates: [water.phila.gov/flat-rock](http://water.phila.gov/flat-rock)***





# Flat Rock Dam

**Overview:** to inform the community about the Flat Rock Dam Betterment Project, share best contact information, and answer questions

## **Project Stakeholders / Partners:**

- Philadelphia Parks and Recreation
- Army Corps Engineers
- PA DEP
- PA Historical Museum Commission (PHMC)
- Manayunk Development Corporation
- National Marine Fisheries Service
- Fish and Wildlife
- Art Commission
- PENNVEST



# Flat Rock Dam

## References:

- Ramboll, O'Brien & Gere Engineers, Inc.: Drone Photos
- Ian McKane, PWD: Photos
- Tom McIntyre, JBC Associates as PWD Inspector: Photos